MYSORE DIVISION.

FORM OF ADVERTISEMENT.

Dated 14th July 1927.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 27th July 1927, for constructing of the New Taluk Lock-up at Nanjangud. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the hours of 11 A.M. and 5 P.M. on all working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of rupees one hundred only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing the New Taluk Lock-up at Nanjangud," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of the probable cost of constructing a Taluk Lock-up Building at Nanjangud :—

No.	Items of work	Per	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Earthwork excavation and filling in basement	C.yd.	0 4 0	95	24
2	Stone jelly in mortar—concrete	C.ft.	0 4 6	884	249
3	Stone in mortor foundation and basement ...	,,	0 7 0	2,532	1,108
4	Burnt brick in chunam—superstructure ...	,,	0 5 6	5,225	1,796
5	Burnt stone slabs, 6" thick cut, fitted and dressed	S.ft.	0 12 0	362	272
6	Burnt brick in chunam. Arch work ...	C.ft.	0 10 0	19	12
7	Teak work, wrought and put up with oiling ...	,,	6 8 0	153·97	1,001
8	Rolled steel girders	Each	16 0 0	3	48
9	Plastering with chunam, two coats ...	Sqr.	4 8 0	74·96	337
10	Roofing with Mysore tiles on teak reepers, nails, etc., complete.	,,	35 0 0	8·38	293
11	Ridge tiles set in mortar	R.ft.	1 0 0	78	78
12	Roofing with brick on edge	Sqr.	40 0 0	9·82	373
13	Teakwood doors with pannelled shutters and iron fittings. etc., complete.	S.ft.	2 8 0	64	160
14	Iron doors with hinges, bolts, etc., for collars as per type design.	,,	4 8 0	17	77
15	Teakwood window with pannelled shutters, iron bars, hinges, hooks, etc., complete.	,,	3 4 0	33	107
16	Ventilators with R. C. perforate 2" thick, complete.	,,	1 12 0	54	99
17	Moulding around door in front, etc.	R.ft.	0 4 0	103	26
18	Corner cut lines as per design in plaster, C. O.	S.ft.	0 1 0	384	24
19	Brick in chunam parapet walls, complete ...	R.ft.	1 8 0	155	232

No.	Items of work	Per	Rate	Quantity	Cost
			Rs. a. p.		Rs.
20	Cornice 9" thick	R.ft.	1 0 0	162	162
21	Honnewood eave board	„	0 6 0	107	40
22	Binding wall over roof	„	0 4 0	28	7
23	Stone brackets below windows	Each	3 8 0	4	14
24	Cement pointing to basement	Sqr.	4 8 0	3·75	17
25	Flooring with Kadaba slabs on 3" concrete and cement pointing.	„	40 0 0	11·29	452
26	Painting with chacolate	„	6 0 0	1·28	8
27	White and colour washing	„	0 7 0	74·96	33
28	Ornamental work and unforeseen ...	Lump	sum		50
	COST OF KITCHEN.				
1	Earthwork excavation	C.yd.	0 4 0	4	1
2	Stone in mud foundation and basement ...	C.ft.	0 4 6	131	36
3	Stone slab 6" thick	S.ft.	0 12 0	50	38
4	Honnewood work	C.ft.	4 8 0	9·37	42
5	Flooring with cement and chunam plastering	S.qr.	6 8 0	64	4
6	Roofing with Mysore tiles on teak reepers, nails, etc., complete.	„	35 0 0	2·08	70
7	Cutting U. shape in pillars	Each	1 0 0	4	4
	COST OF CONSTRUCTING LATRINE.				
1	Earthwork excavation	C.yd.	0 4 0	2	1
2	Stone in mud foundation and basement ...	C.ft.	0 4 6	51	17
3	Brick in mud	„	0 4 6	93	26
4	Plastering with chunam	Sqr.	4 8 0	2·69	12
5	Coping with brick in chunam, chunam plastering.	R.ft.	0 8 0	27	14
6	Constructing drains	„	1 0 0	16	16
7	Constructing cistern	Lump	sum.		6
8	Flooring with concrete	Sqr.	8 0 0	36	3
	Total ...		...	...	7,404
	Contingencies at 5 per cent		...	...	376
	Compensation on lands		...	...	220
	Grand Total ...		...	...	8,000

L. A. H. WINCKLER,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

GOVERNMENT OF MYSORE, STORES PURCHASE COMMITTEE.

Notice No. 203; dated 4th July 1927.

1. Sealed tenders for the supply of Electric Fittings, water pipes and fittings Hardware and other miscellaneous articles required for the Public Works Department and Krishnarajasagara Works during the year 1927-28 will be received by the undersigned up to 12 noon on or before Saturday the 6th August 1927.

2. A sum of Rs. 100 in cash towards earnest money should be remitted to the officer in charge of the State Huzur Treasury, Bangalore, with challans duly filled in by the tenderers, the fact of such remittance being noted in the tenders sent to this office.

The earnest money will not be received here.

3. Forms of tender and challans for remitting earnest moneys may be obtained from the office of the Secretary, Stores Purchase Committee, on payment of Re. one only (in cash only) being the price fixed for the form.

The forms will not be sent by V. P. P.